NOTICE IS HEREBY GIVEN that a special meeting of the Millpond Dam Committee of the Village of Neosho shall be held on **TUESDAY, SEPTEMBER 12,** 6:00 p.m., at the Neosho Village Hall, 210 S. Schuyler Street, Neosho WI.

The village hall is handicap accessible.

TUESDAY, SEPTEMBER 12, 6:00 P.M.

- 1. Swear in new committee members.
- 2. Recap of dam project YTD.
- 3. Timeline review.
- 4. Action item list review.
- 5. Engineering report/company.
 - a. Review Kunkel report and additions needed.
 - b. New engineering company to be hired. Create list of candidates and contact.
- 6. Grants information gathering.
- 7. Emergency action plan updates needed.
 - a. Scan current document to have an electronic copy.
 - b. Review and update.
- 8. Contractors
 - a. Create a list of contractors.
 - b. Contact to determine if qualified and would be interested in bidding.
- 9. Fundraising.
- 10. Q&A. New business.
- 11. Determine next meeting date, time, and agenda items.

Adjournment.

Any additions or corrections will be posted at the Village Hall.

/s/ Deanna Braunschweig, Village Clerk-Treasurer

Any person who has a qualifying disability as defined by the American's With Disabilities Act, that requires the meeting or materials at the meeting to be in an accessible location or format must contact the Clerk-Treasurer at the village hall at 920-625-3086 at least one day prior to the meeting so that any necessary arrangements can be made to accommodate each request.

It is possible that members of or a quorum of members of other governmental bodies of the municipality may be in attendance at the above-stated meeting to gather information. No action will be taken by any other governmental body except by the governing body noticed above.

Neosho Dam Repair Project

Steps		Start	End	% Complete	Notes
Field Inspection Report		7/12/2022		80	further inspection needed & updated documents
Budget		9/12/2023		5	budget info needed for village board Sept. 2024
				0	
Emergency Action Plan Review		8/9/2023		25	submit completed plan to committe
Emergency Action Plan				0	submit to DNR
DNR Permit				0	
Grants				0	grants open September. Need to submit 9/1/2024
Create bid proposal		2/1/2024		0	
Post Bid		12/1/2024		0	
Hire Contractor		2/1/2025		0	
Contractor perform work		spring 2025	8/1/2025	0	
Drop dead date		9/30/2025			All work completed, everything submitted to DNR
Action Items	Owner	Start	End	% Complete	Notes
Kunkel Engineering	Chris	8/9/2023		75	further inspection needed
Emergency Action Plan	Jen/Mike W.	8/9/2023		0	review and update as needed
Additional pictures of dam	Chad	8/9/2023	8/28/2023	100	trunnion pins
Fundraising					
Grants					
Hire new engineering company					
Contractors					list of proposed contractors. Need feedback on project



KUNKEL ENGINEERING GROUP

107 Parallel Street Beaver Dam, WI 53916 Phone (920) 356-9447 / Fax (920) 356-9454

Dam Inspection Memo - September 14, 2021

Chris Oldenhoff, Village President Village of Neosho 210 S Schuyler Street Neosho, WI 53059

RE: Inspection Report for Neosho Dam, FF # 14.14 Seq 1077

Mr. Oldenhoff:

At the request of the Village, I performed a field inspection of the Neosho Dam on July 7, 2022. Your copy of the WDNR Inspection Forms and Photo Log are attached. As you are aware the dam is an earth embankment, approximately 1000 feet long and 12 feet high, carrying State Highway 67. The 74 ft long paved concrete spillway with tainter gate is located under the highway bridge near the south end.

In 1994 the spillway was repaved, pressure grouted, and the steel tainter gate replaced. This inspection shows cracks and spalling have developed on the downstream side of the gate wings. The most serious being a section of the 94 repair on the south wing that is washed away in the splash zone exposing reinforcing steel. This situation currently does not appear to be structurally significant, but must be monitored. As indicated in the 2011 Inspection Report, the steel tainter gate needs to be recoated to prevent further corrosion.

The benchmark at the SE corner of the bridge deck appears to be undisturbed. Required waterway dam signage is in place. The downstream side of the embankment must be periodically monitored for erosion caused by runoff from the highway and WisDOT contacted if maintenance is warranted.

Inspection, Maintenance & Operation Plan were submitted to WDNR on 3/6/2012. WDNR record indicates that to date an Emergency Action Plan and the Dam Failure Analysis have not been completed and submitted. In my opinion, as downstream development has not significantly changed since the last inspection the current Low Estimated Hazard Rating should be maintained.

Gate Recoating Maintenance is required as outlined below, with a target completion of September 30, 2025:

- install temporary dam / dewatering provisions and remove gate
- provide nearby temporary containment for blasting and coating or transport gate to shop.
- sandblast gate and struts, preparing steel surfaces to "near-white blast level"
- apply zinc primer coat, stripe coat, 2nd primer and finish epoxy coat or equal
- inspect and repair/replace gate seals as needed
- reinstall gate and check gate alignment

The report materials are being forwarded to WDNR for review and concurrence with the above timeframe for repairs. Should you need to discuss this work, please call Don Neitzel or myself at your convenience.

regards,

KUNKEL ENGINEERING GROUP


Baril Och

Basil Orechwa PE

Attachments

cc

Uriah Monday, WDNR



Certification for Dam Inspection

Local Dam Name (PRINT): _____NEOSHO DAM

DNR Field File #: 1077

I certify that I have completed the checklist truthfully and factually:

Certifier's Name (print): ________ BASIL ORECHWA

Company Name: KUNKEL ENGINEERING GROUP

Signature: _______________

Date: <u>8-12-2022</u>

Multidisciplinary: I am experienced in the technical disciplines or I am working with other professionals experienced in the technical disciplines to properly inspect this dam and appurtenant works. Technical disciplines, in addition to general civil engineering, may include geotechnical, geological, hydrologic, structural, and mechanical:

Yes No

Engineer's Wisconsin Registration Number: E-32173

Expiration Date: _____7/31/2024

Engineer's Seal (optional):

Name of Dam: NEOSHO DAM Inspectors: BASIL ORECHWA		Date: 7-13	_	_
Inspectors: BASIL ORECHWA Owner's Name: VILLAGE OF N		F.F#: 14.1		-
Street: 210 SOUTH SCHUYLER	itej 5	Seq #: 1077	-	_
City, State, Zip Code: NEOSHO,			-	-
County: DODGE COUNTY	Phone: 920-356-	0447		-
Weather and Site conditions: MC	STLY SUNNY, BREEZY, 80 Email: BORECHV		HC CC	70
feather and one conditions. The	GENERAL		ctio	_
Item				
1 Monuments/Benchmarks	N P Notes/ Observations	M	1	_
Location: Elevation: Datum:	SE CORNER OF THE BRIDGE DECK 884.45 PLAN			
2 Pool Level Normal/Operating:	874.00			
Maximum: Minimum:				
Staff Gage	NO STAFF GAGE			
	S.T.H. 67			
4 Signage/ Security				
Portage/route:				
Dam Warning:	¥			
Downstream Hazard:				
Downstream Hazard: Fencing/Railings/Catwalks:				
Downstream Hazard:				
Downstream Hazard: Fencing/Railings/Catwalks:	Action Suggestion 1. Requires immediate action 2. Plan to do soon			

	GENERA	L (Cont.)			
5 Hazard Section					
A. D/S Development					
Density:					
Distance:		PMENT DOWNSTREAM			
Type (Residential, Commercial,					
Industrial):	<u> </u>		— <u> </u>		
B. Channel Crossing	Duiden Ford Oulwort T	d Other (P. 1-12) (Charle Ore)			L
Dimensions:		restle, Other (Explain) (Circle One)			
Dimensions: D/S distance:					
Traffic Level (Local, CTH,					I
Rail Road, STH, Interstate, etc):					
C. Distance to nearest D/S			<u> </u>		
community/impoundment:	7,300 FEET TO H	ALE ROAD BRIDGE			
Name:					ļ
					ļ
D. Anticipated Hazard (based					
on landuse and zoning):	LOW				
E. Dam Failure Analysis					
Date Completed/Approved					ļ
Is map available?					ļ
Are map & profile adopted?					ļ
List adoption date:					ļ
Verify validity of failure mode:					ļ
					ļ
Verify validity of DFA					
conclusions:					
F. Emergency Action Plan	Y N Cor	mments, Explanation, and Description	M	Ι	R
1. Current plan posted?	✓				
2. Understood by Operator?	✓			 	
3. Warning systems?4. Certification of last test?	V			┝───┥	
5. Remote operation?	V			┝───┤	
6. Revision Date?	V			┝───┤	
7. Habitable structures?	v			├───┤	
8. Recreation areas?	- <u>-</u>				
9. Changed hazard potential?					
10. New development?	- Y			┢━━─┨	
11. Other comments?	\sim			<u> </u>	
Additional Comments:	<u> </u>			I	
N= Noted; P= Photo; M= Monitor	Action Suggestic	on 1. Requires immediate action	_		
I= Investigate; R= Repair		2. Plan to do soon			
F.F. = Field File; \mathbf{RT} = Right; \mathbf{LT} = 1		3 . Do when convenient			
U/S = Upstream; D/S = Downstream					
		nspection Checklist	625	•	~
Dam Name: NEOSHO DAM	F.F. #: 14.14	Date: 7-13-22	Page	3 of	8

	EMBANKMENTS									
Description: EARTHEN EMBANKMENTS Ac								ction		
									М	1 R
	Item	N	P	L	ocat	ion on Embankr	nent and D	eficiency		
1	Vegetation:	\checkmark	No pro					•		-
	A. Trees									
L	Quantity (<5,sparse,dense):		<u> </u>						L	
	Diameter:		PARSE,	TREES LO	CA	FED AT THE END	OF THE DO	OWNSTREAM WIN	GWALI	LS
1	Location:	15	" AND	SMALLER						
	B. Brush								<u> </u>	
	Quantity (sparse, dense):				00					
	Location:	>	PARSE	, BRUSG L	OCA	ATED AT THE EN	D OF THE L	DOWNSTREAM WI	NGWAI	_LS
L										
	C. Ground cover									
	Type (grass, crown vetch,other):	⊢								
Ł	Quantity (bare, sparse, adequate,	R	IPRAP	WITH ASP	HA	LT AT THE TOP O	OF THE EME	BANKMENT		
	dense):									
	Appearance (too tall, too short,									
2	good): Erosion	1	1.	1.1	1	<u> </u>				
4	And the second sec	v	No pro	blem		Not applicable	Could no	of inspect		
	A. Wave erosion (Beaching):	-								
	Scarp: Length/ Width:		NOU		ICIC	NINOTICED				
	Location:		NO W	VAVEERO	ISIC	NN NOTICED				
1										
	B. Runoff Erosion (Gullies)									
	Quantity:						/_			
	Length/ Width/ Depth:		SOM	E RUNOFF	ERO	DISION FROM S.7	Г.Н. 67			
	Location:									
3	Instabilities		No prol	blem		Not applicable	Could no	ot inspect		
	A. Slides									
	Transverse:									
	Longitudinal:									
	Scarp: Length/ Width:	1	NONE							
	Crack Length/ Width:									
	B. Cracks:								20	
	Transverse:									
	Longitudinal:									
!	Length/ Width/ Depth:	ין	NONE							
	Location:		UCIUE							
İ.	Other:									
	C. Bulges/ Depressions									
	Size:								<u> </u>	
	Height/ Depth:	1	NONE							
	D. Slope (Too Steep)			NONE						
L	U/S, D/S								<u> </u>	
N=	= Noted; P= Photo; M= Monitor		Act	tion Sugges	tion	1. Requires imm	ediate action			
	Investigate; R = Repair			55		2. Plan to do soc				
	F. = Field File; $\mathbf{RT} = \text{Right}; \mathbf{LT} = 1$	Lefi	t			3. Do when conv				
	S = Upstream; D/S = Downstream									
ļ-	Additional Comments:									
	~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~									
1										
⊢	Dam Inspection Checklist									
h	am Name: NEOSHO DAM					OIL CHECKIISI	D 4 7	12 2022	D 4	
108	IIII IVAIIIC: IVEOSITO DAM		1.1	F, #: 14.14	_		Date: 7-	-13-2022	P 4	01 8

		EMB.			Actio
Item	N	P	Notes/ OF	oservations	M I
Slope Protection		No problem	Not applicable	Could not inspect	
A. Type (none, riprap, wave berm, concrete slabs, loose formed concrete/asphalt):		RIP RAP			
B. Condition:		IN GOOD	O CONDITION		
Other	\checkmark	No problem	Not applicable	Could not inspect	
A. Rodent burrows (few, many) Location:		NONE			
B. Ruts Length/ Width/ Depth: Location:		NONE			
C. Other					
Alignment	~	No problem	Not applicable	Could not inspect	
A. Vertical Low area: Elevation Difference: Location:		NONE			
B. Horizontal		NONE			
C. Width Too narrow: Location:		ROADWA	AY (S.T.H. 67) GOOD		
Тое	\checkmark	No problem	Not applicable	Could not inspect	
Cracks/Slumps: Embankment drains: Type/Flow: Location: Seepage/ Wetness: Hummocky:		NONE			
Seepage	V	No problem	Not applicable	Could not inspect	
Wet area: Boil: Sinkhole: Aquatic vegetation: Rust colored deposits: Other: Sediment in Flow: Flowrate: Location:			DNE		
Noted; P= Photo; M= Monitor Investigate; R= Repair F.= Field File; RT = Right; LT = S = Upstream; D/S = Downstream Additional Comments:		Action Sugge	estion 1. Requires imm2. Plan to do so3. Do when con	on	
		Dam Inc	pection Checklist		

	SPILLWAYPRINCIPAL - FIXED CREST Action							
Item	N	<u> </u>		Notes/ Observation	ons	Μ	Ι	R
1 Fixed Crest	\checkmark	N	o problem	Not applicable	Could not inspect			
A. Dimensions Top Width:	-	V	30' SOUTH AND 30	' NORTH				
B. Materials		[
C. Shape (sharp-crested, broad-crested, ogee, chute, gated, overflow, morning glory, dropbox, labyrinth) D. Debris		I I	J BROAD CRESTED				[
Prevention (racks, booms, etc.): E. Concrete Condition *		[NONE				1	
		·	OK. INVESTIGATE E SOUTH SPILLWAY	EXPOSED IRON ON E	3ACK OF	·	v	
F. Flashboards (none, number): Type (Metal, wood): Dimensions: Operability:		!	NONE				[
G. Abutments Condition: * Seepage/wetness:			GOOD					
H. Drains Type: Weep holes, Relief drains, Other: Flow Rate:		No	o problem	Not applicable	Could not inspect			
I. Other								
N= Noted; P= Photo; M= Monitor I= Investigate; R= Repair F.F.= Field File; RT = Right; LT = U/S = Upstream; D/S = Downstream		t		Requires immediate act Plan to do soon Do when convenient Uncontrolled = O				
Additional Comments:								
* Type of Concrete Problems:	Spa	llinį	g, cracks, exposed rebar, 1	nisalignment, joints, bu	ng holes, efflorescence, popo	outs,		
	110	iey	combing, scaling, craze/m Dam Inspectio					
Dam Name: NEOSHO DAM			<u>F.</u> F.#: 14.14		Date: 7-13-2022	6	of	8

T4	BT	pI	SI ILLWA	Y-PRINCIPAL - GAT		Acti
Item	-	P		Notes/ Observati		MI
Gates	\checkmark	No	oroblem	Not applicable	Could not inspect	
A. Types (lift/slide, tainter(radial),		\checkmark				
stoplogs, leaf, roller, flashboards, needles, other):		іліт	FD	CORROSION ON GA	ТЕ	
flashboards, needles, other): Number and Size:		1111	ER			
B. Stoplogs		T				
D. Stoplogs Dimensions:			NT/ 4			
Condition:			N/A			
C. Abutments		1				
Condition: *	<u> </u>	-	GOOD CONDITIO	N		
Seepage/wetness:	I		GOOD CONDITION	1 1		
D. Piers (number, shape)	1 1	~	2 PIERS, BOTH H	IAVE MINOR SURFAC	E SPALLING/	\checkmark
Condition: *		- 1	CRACKING.			
E. Operability	 	\checkmark				
Type of Operator:			CABLE AND C	CRANK		
Condition(chain, cables, hoists):						
Security(locked?):						
Backup Operator:	L.,	-				
F. Access	Ш		BRIDGE DECK	FROM STH 67		
G. Condition		√				
Rust:		-		DOTS		
Seals (leakage):		ATE	IS RUSTING IN SH	2018		
H. Ice protection		Т				
Type (Heaters, Bubblers,			N/A			
Barriers, Other)						
I. Debris						
Prevention (Rack, boom, etc.)			N/A			
I. Condition - f El-	-	1				
J. Condition of Flowway	\vdash		GOOD			
			0000			
K. Drains		Т				
Type (Weep holes/ Relief drains/						
Other):			N/A			
Flow rate:			1N/A			
Location:						
L. Other						
		_				
Matadi D- Dhatai M- Manitan			Action Suggestion	1. Requires immediate ac	tion	
				2. Plan to do soon		
nvestigate; R = Repair	1 0					
Noted; P= Photo; M= Monitor Investigate; R= Repair := Field File; RT = Right; LT = S = Upstream; D/S = Downstream			Controlled = Gated	3. Do when convenient Uncontrolled = 0		

	SPILLWAYPRINCIPAL - OUTLET EROSION CONTROL & UNDERMINING							
				A	etio	n		
	Item	NP	Notes/ Observations	M	Ι	R		
1	Outlet Erosion Control	No problem	Not applicable Could not inspect					
	A. Type (none, endwall, plunge pool, energy dissipation structure rock lined channel, apron)	ENERGY DISSIPATION	STRUCTURE					
	B. Scour							
	C. Material							
	a. Riprap: Avg Diameter: Condition (adequate, sparse, displaced, weathered): Bedding fabric- (Yes/ No): b. Concrete * Dimensions/Location:		GOOD SHAPE					
	D. Sidewall/Headwall							
	Misalignment: Location: Description:	GOOD CONDITION						
	E. Separated Joint / Loss of							
	Joint Material: Location: Description:	N/A						
	F. Natural	N/A						
	TT 1 4 4							
2	Undermining Location:	No problem	Not applicable Could not inspect	- <u> </u>				
	Description:	NONE			1			
I= F.1 U/3	Noted; P= Photo; M= Monitor Investigate; R= Repair F.= Field File; RT = Right; LT = S = Upstream; D/S = Downstream	2. Left 3.	Requires immediate action Plan to do soon Do when convenient Uncontrolled = Overflow					
Ad	ditional Comments:							
*	Type of Concrete Problems: S	Spalling, cracks, exposed rebar, r	nisalignment, joints, bug holes, efflorescence hap cracks, isolated crack, disintegration, oth	e, popouts,				
		Dam Inspectio						
Da	m Name: NEOSHO DAM	F.F.#: 14.14	Date: 7-13-2022	Page 8	of	8		



Village of Neosho, Dodge Co Neosho Dam Inspection Photo Log

Date of Inspection & Photos 7/12/2022


Key Sequence # MM/DD/YYYY Photo# Discription

J			I
1077	7/12/2022	1	North upstream embankment
1077	7/12/2022	2	South spillway, upstream view
1077	7/12/2022	3	South spillway, overhead view
1077	7/12/2022	4	South spillway abutment
1077	7/12/2022	5	Overhead view of tainter gate
1077	7/12/2022	6	Tainter gate itself
1077	7/12/2022	7	Tainter Gate, North pin corrosion at North point
1077	7/12/2022	8	Overhead view of south pier
1077	7/12/2022	9	Overhead view of north pier
1077	7/12/2022	10	Upstream view of north abutment
1077	7/12/2022	11	Upstream view of north spillway
1077	7/12/2022	12	Upstream north embankment
1077	7/12/2022	13	Upstream north embankment
1077	7/12/2022	14	Downstream view of south spillway and abutment
1077	7/12/2022	15	Downstream view of tainter gate
1077	7/12/2022	16	downstream view of north abutment
1077	7/12/2022	17	Overhead view of south abutment
1077	7/12/2022	18	Look downstream fro bridge over dam

Neosho (Mill Pond) Dam



0107707122022 1



0107707122022 3



0107707122022 2




Neosho (Mill Pond) Dam




0107707122022 6



0107707122022 8



0107707122022 7



Neosho (Mill Pond) Dam



0107707122022 10




0107707122022 11





0107707122022 12

Neosho (Mill Pond) Dam



0107707122022 14



0107707122022 16



0107707122022 15



Neosho (Mill Pond) Dam

